



GAF MATERIALS CORPORATION

11800 Industry Avenue Fontana CA 92337 • Tel: 951.360.4200 • Fax: 951.681.2719

October 8, 2009

TO: CERTIFIED GAF CONTRACTORS

FROM: GAF FIELD OPERATIONS

REFERENCE: CHURCH OF JESUS CHRIST OF LATTER DAY SAINTS
VERNAL UTAH ASHLEY STAKE DAVIS 1 & 4 WARDS – ADDITION
GAF GUARANTEE E193046-00 GAF GUARANTEE E1660307-01
235 EAST 600 SOUTH 3990 S. 1500 EAST
VERNAL, UT 84078 VERNAL, UT 84078

SUBJECT: GAF RUBEROID SPECIFICATION -I-1-2-20-MGPFR REQUEST FOR PROPOSAL

GAF is requesting a proposal for the following scope of work on the above Guaranteed roof assemblies to address the slippage of the SBS RUBEROID membrane. The assemblies consist of an insulated deck, base sheet, RUBEROID 20 and RUBEROID Mop Plus FR, set in hot asphalt.

Ashley Stake Building:

- Approximately 800 LF of RUBEROID 20 exposed from slipping membrane.
- Trim membrane overhanging at the edge, approximately 200 LF
- Cut out the buckled areas and fish mouths
- Prime the existing RUBEROID membrane to be torched
- Torch RUBEROID modified APP Granulated cap sheet (white) no less than 12" wide over exposed ply
- Some of the areas will require a full width less the salvage edge to cover
- Be sure there is at least 6" of membrane past the patch areas in all directions

Davis First and Fourth Wards Building:

- Approximately 500 LF of exposed RUBEROID 20 due to slipping membrane
- Trim off membrane at drip edge that is hanging over, approximately 100 LF
- Prime the existing RUBEROID membrane to be torched
- Torch RUBEROID modified APP granulated cap sheet (white) at least 12" wide over exposed ply
- Some of the wider areas will require a strip 16" wide, totaling approximately 500 LF
- Be sure there is at least 6" of membrane past the patch areas in all directions

Proposals to include all materials, labor, insurance, and permits to successfully complete these projects. This will be a lump sum proposal for both projects. Proposals due October 15th 2009 5:00 PM west coast time. Please email to jpohorsky@gaf.com or facsimile to 951-681-2719. Do not conduct a site inspection without scheduling through GAF's Ed Ashley; 801-598-6430.

Regards,

GAF

John Pohorsky, RRC
Field Operations

Cc: Project files, Ed Ashley

AshleyandDavisLDSRequestForProposal.doc